

Boston Freightliner



3 Air Force Rd

Everett, MA 02149

Completed: 2018	Duration: 12 Months
Project Size: 75,000 SF	GC: CM&B
Engineer: BALA TMP	Value: \$865,000



Design • Sales • Installation • Consulting

267 Boston Rd. Ste #16 N. Billerica, MA 01862 • Office: 978-262-0003

- New construction -repair facility
- (3) Energy recovery units. CFM ranging from 5,000cfm to 10,000cfm
- VAV rooftop unit supply air to VAV boxes with hot water reheat coils.
- (2) 1600 MBH Hot water boilers serving VAV boxes, unit heaters and energy recovery unit.
- Waste oil furnace.
- HVAC system controlled by DDC System

